Sl. No.	Description of Items
1	Excavation for road, drains and similar works - KSRRB300-2. Earthwork excavation manual means in ordinary soil involving an average horizontal throw up 2 meters a an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed t disposed earth to be leveled neatly after breaking of clods complete as per specificati and direction of enginner in charge of the work
2	Providing and laying in positon plain cement concrete of mix M 7.5 with OPC cement @ 1 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum a fine aggregates @ 0.57 cms. Thick, well commpacted in foundation and plinth, includi cost of all materials, labours HOM of machinery curing complete as per specification a direction of engineer in charge of the work.
3	Providing and laying in position plain cement concrete of mix M 1:2:4 with cement @ 2 kgs, with 20mm and down size graded granite metal coarse aggreates @ 0.878cum a fine aggreagates @ 0.459cum machine mixed, concrete laid in layers not exceedi 15cms thick, well compacted in foundation and plinth, including cost of all materials labo HOM of machinery curing complete as per specification and direction of engineer in char of the work
4	Providing Granite slabs selected quality roughly dressed and fixed in cement (1:6) includi fixing curing etc., complete as per specification and direction of engineer in charge of t work.
5	Providing and constructing precast concrete solid blocks with compressive strength not le than 35 kgs/ sqm with cement mortar 1:4 masonry (quoin Jamb, closer, blocks) with so concrete blocks of size 40x20x20 cms conforming to I.S 2185/1965 in superstrctu including cost of materials, labour chargfe scaffolding, curing complete as per specificati
6	Supplying and fixing precaste rainforced concrete slab 10cm thick including cost reinforcement as per design and drawing material cost, transportation, hire charges machinery machine cutting the vertical face to get plain even surface labour charg inclusive of cost of all materials, complete as per specification and direction of engineer charge of the worik
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by t enginner in charge of the work lead 4 Km a) Basic rate for halage of mateirals as pe ite average earrth of work 1.28 Tonne/Km for Rs. 2.00 /Km c) Add loading and unloadi complete as per specificaion and direction engineer in charge of the work

CERTIFICATE

1 This is to certify that the contractor has completed the work satisfactorily.
2 The contractor has cleared the debries from the work sport
3 The contractor has used his own vehicles for the coveying the debries.
4 There are no departmental issues for the above work.

ಕಿರಿಯ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಜಿ. ದಾಸರಹಳ್ಳಿ ಉಪ ವಿಭಾಗ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಬಾಗಲಗುಂಟೆ, ಬೆಂಗಳೂರು - 560 073